

Enquiries: Vinay Gupta
Our Ref: RDS/00179



To the Resident
Important information inside
Road Resurfacing



23 March 2026

Dear Resident,

Notification of works

The Town would like to advise the following upcoming project:

Type of works:	Drainage installation Kerb reinstatement Road resurfacing works
Location:	Bernard Street – Goldsworthy Road to the end
Commencement date:	Tuesday, 7 April 2026
Estimated completion date:	Wednesday, 29 April 2026

Whilst the aim is to start and complete the works by the dates indicated above, this is dependent on weather conditions and contractor availability.

Below is the general sequence of events:

Weeks 1 and 2

- Drainage will be installed.
- Removal of old or damaged kerb.
- This includes removal of some small sections of crossovers at the road edge (typically asphalt and brick paved crossovers).
- Install new kerb (typically fully mountable or semi mountable). This includes areas in front of crossovers where removed.
- There will be a minimum 2-day gap following this to allow the concrete kerb to cure.
- Reticulation will be cut and capped for later reinstatement.

Weeks 3 and 4

- Removal of the existing asphalt road surface for the entire length and width of the road to a maximum depth of 30mm. **Please note that there will be limited access to properties during asphalt works.**
- Backfill behind kerbs.
- Reinstating crossovers as required.
- Provide a general clean up inclusive of reticulation repairs.

If you have any vegetation growing close to the road, please ensure it is pruned back or removed to a minimum of 600mm from the edge of the existing road prior to Monday, 6 April 2026. If this has not been completed by that time, the Town's Parks Team or appointed contractor may undertake the pruning or removal of any vegetation encroaching into this area. While all reasonable care will be taken, any plants, trees, or vegetation located within this zone may be at risk of damage or removal during the works.

Some crossovers may need to be modified by the Town's contractor to better match the edge levels of the newly constructed road. When this occurs, please do not move the cones or other traffic management devices, as concrete that has been laid may be curing or new asphalt cooling. During this time alternate arrangements may need to be made when accessing your property, for a maximum period of 24 hours to allow for concrete curing. We will discuss this with you if it is required on a case-by-case basis.

Please note that during construction, access to the road will be restricted. Access to properties will still be allowed, unless advised by traffic management due to safety concerns on the day. Some detours and traffic management will be erected to allow vehicles to travel around the site safely to ensure the safety of the Town's staff, contractors, and the public.

The Town will repair any damaged irrigation on verges caused by our works and will organise testing of systems once works are complete. Please ensure you contact the Town within one month of the completion date if any issues have yet to be addressed regarding damage.

While it is inevitable that works of this nature will cause inconvenience, every effort will be made to ensure that this is kept to a minimum. An *information sheet* has been attached that will answer most common queries that arise while the works are occurring.

If you have any questions regarding this project or would like further information, please contact me on 0409 725 062.

Yours sincerely



Vinay Gupta
Project Officer – Works